



SALIENT TECHNICAL FEATURES

“Salient Technical Features of the systems /equipment/ services are mentioned below. These Salient Technical Features are mentioned only to facilitate the prospective bidders to prima-facie understand the requirements under the tender and shall not in any way limit or alter the scope of work and technical features/specification of equipment/ systems/ services covered in the Bidding Documents. Detailed provisions in regard of scope of work and technical features/specification of equipment/ systems/ services, contained in the Bidding Document shall be final and binding.”

Salient technical features of the proposed project are as follows:

Name of the Project	Development of “ EPC PACKAGE FOR DEVELOPMENT OF 250MW (1X250MW) GRID CONNECTED SOLAR PV PROJECT AT BIKANER, RAJASTHAN ”
Project capacity	250 MW (1 Block of 250 MW), Timeline ~15 Months
Block/Plot capacity	One Block of 250MW

1. One Block of 250 MW Solar Photovoltaic Power Project as EPC Package.
2. Complete Design, engineering, manufacturing, supply, packing and forwarding, transportation, unloading storage, installation, testing and commissioning of Solar Photo Voltaic Plant **including** supply of Solar PV Modules.
3. **MMS** as per Technical Specification – Tracker based (**Cost per MU Based Bidding**)
4. String / Central Inverter with minimum cumulative capacity of 250 MW with Maximum Power Point Tracking technology along with associated cables, cabling, Transformer & Switchgears.
5. SCADA, Weather Monitoring System, and CCTV system.
6. Electrical works and associated switchgear equipment as per technical specification.
7. Evacuation of power up to Owner’s 33kV Switchgear of 33/400kV Substation
8. Module cleaning system including supply and installation of all accessories.
9. All associated civil works for Solar plant and power evacuation up to Owner’s 33kV Switchgear of 33/400kV Substation
10. Dynamic reactive power compensation at Pol as per CEA technical standards and working committee report.



NTPC Renewable Energy Limited

(A wholly Owned Subsidiary of NTPC Limited)

Corporate Centre

11. Facilitation for Grid compliance study of Solar projects
12. Comprehensive O&M for 3 years from date of commissioning of full capacity
13. Supply of mandatory spares